



STANDARD 6'-0" EXTENSION:

1. REMOVE ONE EXISTING END POST.
2. INSTALL NEW LINE POST AT PREVIOUS POST POSITION.
3. ATTACH NEW TOP RAIL AND MID RAIL TO LINE POST. HAND TIGHTEN SETSCREWS.
4. ATTACH EXISTING END POST TO TOP RAIL AND MID RAIL. HAND TIGHTEN SETSCREWS.
5. ANCHOR NEW POST POSITION. ANCHORS NOT PROVIDED.
6. USING A LEVEL, CHECK THAT POST ARE VERTICAL AND RAILS ARE LEVEL.
7. TIGHTEN ALL SETSCREWS.

THIS DRAWING AND ALL THE INFORMATION THEREON IS THE PROPERTY OF THE HOLLANDER MFG. CO., IS CONFIDENTIAL AND MUST NOT BE MADE PUBLIC, NOR COPIED, NOR USED, TO THE DISADVANTAGE OF SAID HOLLANDER MFG. CO. AND IS SUBJECT TO RETURN ON DEMAND.

COPYRIGHT 2013, HOLLANDER MANUFACTURING CO.

NO.	REVISIONS	DATE	APPROVED
0	RELEASED FOR APPROVAL	1-15-13	BW

Hollander
 STRUCTURAL ENGINEERING GROUP
 10285 WAYNE AVENUE
 CINCINNATI, OH 45215-6399
 PHONE: (800) 772-8800 FAX: (502) 772-8806
 WWW.HOLLANDER.COM

PROJECT	CUSTOMER	DESCRIPTION
EXTENSION RAIL SECTION 6'-0" c/c POST 42" HIGH RAIL		MODULAR RAIL SECTION DRAWINGS

DRW NO.	APP'D BY	DATE
GG	BW	1-15-12
50330		NTS
MILL		7064-S
ALUM. PIPE/ALUM FITTING		1 of 1

